

AD-A105 333

WOODWARD-CLYDE CONSULTANTS CHICAGO IL

F/6 13/13

NATIONAL DAM SAFETY PROGRAM. KEYES BRANCH MINE DAM (MO 30386). --ETC(U)

AUG 80 R G BERGGREEN, J PEREZ

DACW43-80-C-0066

UNCLASSIFIED

NL

1 OF 1  
AD A  
10-3,34

END  
DATE  
FILMED  
11-81  
DTIC

**LEVEL** # (1)

## MISSISSIPPI-KASKASKIA-ST. LOUIS BASIN

KEYES BRANCH MINE DAM  
WASHINGTON COUNTY, MISSOURI  
MO 30386

### PHASE 1 INSPECTION REPORT NATIONAL DAM SAFETY INSPECTION



United States Army  
Corps of Engineers

... Serving the Army  
... Serving the Nation

**St. Louis District**

**DTIC**

**EL**

**OCT 13 1981**

**A**

PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

AUGUST 1980

This document has been approved  
for public release and sale; its  
distribution is unlimited.

"Original contains color  
plates: All DTIC reproductions  
will be in black and  
white"

81 10 9 018

AD A105333

ONE COPY

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM	
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER	
	AD-105333	9	
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Keyes Branch Mine Dam (MO 30386) Washington County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report	
7. AUTHOR(s) Woodward-Clyde Consultants		6. PERFORMING ORG. REPORT NUMBER	
		8. CONTRACT OR GRANT NUMBER(s) DACW43-80-C-0066	
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 11	
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		12. REPORT DATE August 1980	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) (6) National Dam Safety Program. Keyes Branch Mine Dam (MO 30386), Mississippi - Kaskaskia - St. Louis Basin, <del>Washington</del> Washington County, Missouri. Phase I Inspection Report.		13. NUMBER OF PAGES Approximately 70	
16. DISTRI	15. SECURITY CLASS. (of this report) UNCLASSIFIED		
Approved for release; distribution unlimited.		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE 12 61	
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) (1) Foran G/E... Jean-Yves/P...			
18. SUPPLEMENTARY NOTES			
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams			
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.			

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

411445

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

b3

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

## INSTRUCTIONS FOR PREPARATION OF REPORT DOCUMENTATION PAGE

**RESPONSIBILITY.** The controlling DoD office will be responsible for completion of the Report Documentation Page, DD Form 1473, in all technical reports prepared by or for DoD organizations.

**CLASSIFICATION.** Since this Report Documentation Page, DD Form 1473, is used in preparing announcements, bibliographies, and data banks, it should be unclassified if possible. If a classification is required, identify the classified items on the page by the appropriate symbol.

### COMPLETION GUIDE

**General.** Make Blocks 1, 4, 5, 6, 7, 11, 13, 15, and 16 agree with the corresponding information on the report cover. Leave Blocks 2 and 3 blank.

**Block 1.** Report Number. Enter the unique alphanumeric report number shown on the cover.

**Block 2.** Government Accession No. Leave blank. This space is for use by the Defense Documentation Center.

**Block 3.** Recipient's Catalog Number. Leave blank. This space is for the use of the report recipient to assist in future retrieval of the document.

**Block 4.** Title and Subtitle. Enter the title in all capital letters exactly as it appears on the publication. Titles should be unclassified whenever possible. Write out the English equivalent for Greek letters and mathematical symbols in the title (see "Abstracting Scientific and Technical Reports of Defense-sponsored RDT/E," AD-667 000). If the report has a subtitle, this subtitle should follow the main title, be separated by a comma or semicolon if appropriate, and be initially capitalized. If a publication has a title in a foreign language, translate the title into English and follow the English translation with the title in the original language. Make every effort to simplify the title before publication.

**Block 5.** Type of Report and Period Covered. Indicate here whether report is interim, final, etc., and, if applicable, inclusive dates of period covered, such as the life of a contract covered in a final contractor report.

**Block 6.** Performing Organization Report Number. Only numbers other than the official report number shown in Block 1, such as series numbers for in-house reports or a contractor/grantee number assigned by him, will be placed in this space. If no such numbers are used, leave this space blank.

**Block 7.** Author(s). Include corresponding information from the report cover. Give the name(s) of the author(s) in conventional order (for example, John R. Doe or, if author prefers, J. Robert Doe). In addition, list the affiliation of an author if it differs from that of the performing organization.

**Block 8.** Contract or Grant Number(s). For a contractor or grantee report, enter the complete contract or grant number(s) under which the work reported was accomplished. Leave blank in in-house reports.

**Block 9.** Performing Organization Name and Address. For in-house reports enter the name and address, including office symbol, of the performing activity. For contractor or grantee reports enter the name and address of the contractor or grantee who prepared the report and identify the appropriate corporate division, school, laboratory, etc., of the author. List city, state, and ZIP Code.

**Block 10.** Program Element, Project, Task Area, and Work Unit Numbers. Enter here the number code from the applicable Department of Defense form, such as the DD Form 1498, "Research and Technology Work Unit Summary" or the DD Form 1634, "Research and Development Planning Summary," which identifies the program element, project, task area, and work unit or equivalent under which the work was authorized.

**Block 11.** Controlling Office Name and Address. Enter the full, official name and address, including office symbol, of the controlling office. (Equates to funding/sponsoring agency. For definition see DoD Directive 5200.20, "Distribution Statements on Technical Documents.")

**Block 12.** Report Date. Enter here the day, month, and year or month and year as shown on the cover.

**Block 13.** Number of Pages. Enter the total number of pages.

**Block 14.** Monitoring Agency Name and Address (if different from Controlling Office). For use when the controlling or funding office does not directly administer a project, contract, or grant, but delegates the administrative responsibility to another organization.

**Blocks 15 & 15a.** Security Classification of the Report: Declassification/Downgrading Schedule of the Report. Enter in 15 the highest classification of the report. If appropriate, enter in 15a the declassification/downgrading schedule of the report, using the abbreviations for declassification/downgrading schedules listed in paragraph 4-207 of DoD 5200.1-R.

**Block 16.** Distribution Statement of the Report. Insert here the applicable distribution statement of the report from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 17.** Distribution Statement (of the abstract entered in Block 20, if different from the distribution statement of the report). Insert here the applicable distribution statement of the abstract from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 18.** Supplementary Notes. Enter information not included elsewhere but useful, such as: Prepared in cooperation with . . . Translation of (or by) . . . Presented at conference of . . . To be published in . . .

**Block 19.** Key Words. Select terms or short phrases that identify the principal subjects covered in the report, and are sufficiently specific and precise to be used as index entries for cataloging, conforming to standard terminology. The DoD "Thesaurus of Engineering and Scientific Terms" (TEST), AD-672 000, can be helpful.

**Block 20.** Abstract. The abstract should be a brief (not to exceed 200 words) factual summary of the most significant information contained in the report. If possible, the abstract of a classified report should be unclassified and the abstract to an unclassified report should consist of publicly-releasable information. If the report contains a significant bibliography or literature survey, mention it here. For information on preparing abstracts see "Abstracting Scientific and Technical Reports of Defense-Sponsored RDT&E," AD-667 000.



**DEPARTMENT OF THE ARMY**  
**ST. LOUIS DISTRICT, CORPS OF ENGINEERS**  
**210 TUCKER BOULEVARD, NORTH**  
**ST. LOUIS, MISSOURI 63101**

REPLY TO  
ATTENTION OF

**SUBJECT: Keyes Branch Mine Dam (MO 30386)**

This report presents the results of field inspection and evaluation of the Keyes Branch Mine Dam. It was prepared under the National Program of Inspection of Non-Federal Dams.

GRAINED.

12 SEP 1980

**SUBMITTED BY:**

Chief, Engineering Division

Date

**SIGNED**

12 SEP 1980

**APPROVED BY:**

Colonel, CE, District Engineer

Date \_\_\_\_\_

Application For  
FBI GRA&I  
LEAD TAB  
Announced  
Classification

**KEYES BRANCH DAM**  
County, Missouri  
Missouri Inventory No. 30386

**Phase I Inspection Report**  
**National Dam Safety Program**

Prepared by

**Woodward-Clyde Consultants**  
Chicago, Illinois

Under Direction of  
St Louis District, Corps of Engineers

for  
Governor of Missouri  
August 1980

## **PREFACE**

*This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams for Phase I Investigations. Copies of these guidelines may be obtained from the Office of the Chief of Engineers, Washington, D. C., 20314. The purpose of a Phase I investigation is not to provide a complete evaluation of the safety of the structure nor to provide a guarantee on its future integrity. Rather the purpose of the program is to identify potentially hazardous conditions to the extent they can be identified by a visual examination. The assessment of the general condition of the dam is based upon available data (if any) and visual inspections. Detailed investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify the need for more detailed studies. In view of the limited nature of the Phase I studies no assurance can be given that all deficiencies have been identified.*

*In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with any data which may be available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action removes the normal load on the structure, as well as the reservoir head along with seepage pressures, and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.*

*It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected, so that corrective action can be taken. Likewise continued care and maintenance are necessary to minimize the possibility of development of unsafe conditions.*



PHASE I REPORT  
NATIONAL DAM SAFETY PROGRAM

Name of Dam	Keyes Branch Mine Dam
State Located	Missouri
County Located	Washington
Stream	Unnamed Tributary of Keyes Branch Creek
Date of Inspections	15 May 1980; 5 June 1980

↓  
Keyes Branch Mine Dam, Identification Number 30386, was inspected, by Richard Berggreen (engineering geologist), James Burnett (geotechnical engineer), Jean-Yves Perez (project manager and geotechnical engineer), and Sean Tseng (hydrologist).

The dam inspection was made following the guidelines presented in the "Recommended Guidelines for Safety Inspection of Dams". These guidelines were developed by the Chief of Engineers, U.S. Army, Washington, D.C., with the help of federal and state agencies, professional engineering organizations, and private engineers. The resulting guidelines are considered to represent a consensus of the engineering profession. They are intended to provide an expeditious identification, based on available data and a visual inspection of those dams which may pose hazards to human life or property. In view of the limited nature of the study, no assurance can be given that all deficiencies have been identified.

↓  
Based on the criteria in the guidelines, the dam is judged to be in the significant hazard classification. The estimated damage zone extends approximately 10 mi downstream. The apparently occupied structures downstream from the dam appear to be above potential flood levels. Damage and loss of life would likely be restricted to traffic on state highways and railroads which cross the creek. The closest state road is approximately 1.6 mi downstream.

Keyes Branch Mine Dam is in the intermediate size classification based on its maximum height of 57 ft, and on its maximum reservoir storage volume of 1400 ac-ft.

Our inspection and evaluation indicate the dam to be in a fair to good condition. A slump-type landslide on the downstream face of the embankment, where sliding had been described earlier by the Missouri Geological Survey, suggests continuing instability at this location.

↑

The erosion potential of the spillway walls and discharge channel appears to be significant. Mining and processing operations at the facility have been discontinued as of December 1979 and no plans were formed by the owner for any future maintenance or inspections of the dam. In light of the discontinued operations and the erosion potential of the spillway facilities, deterioration sufficient to pose a hazard to the stability of the dam could occur in the future without being noticed.

As a result of the erosion potential of the spillway, it was calculated that discharge through the spillway of more than  $170 \text{ ft}^3/\text{s}$  or discharge velocity greater than  $3.5 \text{ ft/sec}$  will significantly erode the spillway to a degree such that this discharge will have the same effects as overtopping the embankment. Based on this analysis, the spillway cannot safely pass a flood of greater than 23 percent of the PMF without effectively overtopping the dam. The PMF is defined as the flood event that may be expected to occur from the most severe combination of critical meteorologic and hydrologic considerations that are reasonably possible in the region. A flood with 1 percent probability-of-occurrence will safely pass the spillway.

Based on our inspection of the Keyes Branch Mine Dam, it is recommended that further study be conducted without undue delay under the guidance of an engineer experienced in the design and construction of dams, to evaluate, as a minimum, the following topics:

1. What spillway capacity should be provided, and in what manner, taking into consideration the high potential erodibility of the embankment materials in the event of overtopping.
2. Potential for erosion during period of heavy flow within the spillway and adjacent portion of the embankment, including erosion mitigating options.
3. Potential for erosion and lateral migration in the discharge channel, including erosion mitigating options.

It is recommended that an inspection and monitoring program be initiated for this facility. This program should include:

1. Inspection of erosion in spillway to evaluate deterioration of the coarse tailings dike on the south side of the spillway;
2. Inspection of lateral and headward erosion in the discharge channel to evaluate potential for undermining the toe of the dam by migration of the discharge channel;
3. Monitoring seepage in the discharge channel and at the toe of the dam to identify changes in the amount of flow and turbidity of the seepage water; and
4. Evaluation of alternatives for an effective, practical warning system to alert downstream residents and traffic on the highways and railroads which cross the drainage if an unsafe condition should develop.


In view of the slide which occurred in the interval between two inspection visits, it is recommended that an analysis be made of the static and seismic stability of the existing structure. An engineering analysis should also be made to identify and design erosion control alternatives for the spillway and discharge channel. This analysis should be conducted by an engineer experienced in the design and construction of dams.

It is suggested that the owner takes action on these recommendations in the near future to preclude deterioration which could lead to the development of hazardous conditions at this facility.

WOODWARD-CLYDE CONSULTANTS



Richard G. Berggreen  
Registered Geologist



Jean-Yves Perez, PE  
Vice President



## OVERVIEW

# KEYES BRANCH MINE DAM

MISSOURI INVENTORY NO. MO 30386

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
KEYES BRANCH MINE DAM - MISSOURI ID. No. 30386

TABLE OF CONTENTS

<u>Paragraph No.</u>	<u>Title</u>	<u>Page No.</u>
SECTION 1 - PROJECT INFORMATION		
1.1	General	1
1.2	Description of Project	2
1.3	Pertinent Data	4
SECTION 2 - ENGINEERING DATA		
2.1	Design	7
2.2	Construction	7
2.3	Operation	7
2.4	Evaluation	8
2.5	Project Geology	8
SECTION 3 - VISUAL INSPECTION		
3.1	Findings	10
3.2	Evaluation	12
SECTION 4 - OPERATIONAL PROCEDURES		
4.1	Procedures	13
4.2	Maintenance of Dam	13
4.3	Maintenance of Operating Facilities	13
4.4	Description of any Warning System in Effect	13
4.5	Evaluation	13
SECTION 5 - HYDRAULIC/HYDROLOGIC		
5.1	Evaluation of Features	14

Paragraph No.

Title

Page No.

SECTION 6 - STRUCTURAL STABILITY

6.1	Evaluation of Structural Stability	16
-----	------------------------------------	----

SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1	Dam Assessment	18
7.2	Remedial Measures	18

REFERENCES

APPENDICES

A	Photographs
B	Hydraulic/Hydrologic Data and Analyses
C	Letter Report on Milchem-Keyes Branch Tailings Pond from Missouri Geological Survey

FIGURES

1.	Site Location Map
2.	Drainage Basin and Site Topography
3a.	Cross-Section and Surveyed Crest Elevation
3b.	Cross-Section and Plan of Spillway
4.	Regional Geologic Map

LIST OF PHOTOGRAPHS

1.	Downstream Face of Dam Looking North
2.	Rock Cover on Face of Dam Looking South (Note Marshy Area at Toe of Dam)
3.	Spillway at Left Abutment, Looking Upstream (West)
4.	Eroded Discharge Channel Below Spillway, Looking Downstream (East)
5.	Erosion Downstream of Discharge Channel, Looking Upstream (West)
6.	Area Downstream of Dam, Looking Upstream (West), Dam in Background
7.	Discharge Flume from Processing Plant, Looking Northeast Toward Dam
8.	Filled Reservoir Area, Looking North-Northeast Toward Dam
9.	Slide on Downstream Face

**PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
KEYES BRANCH MINE DAM, MISSOURI ID. No. 30386**

**SECTION I  
PROJECT INFORMATION**

**1.1 General**

- a. **Authority.** The National Dam Inspection Act, Public Law 92-367, provides for a national inventory and inspection of dams throughout the United States. Pursuant to the above, an inspection was conducted of the Keyes Branch Mine Dam, Missouri Inventory Number 30386.
- b. **Purpose of inspection.** "The primary purpose of the Phase I investigation program is to identify expeditiously those dams which may pose hazards to human life or property... The Phase I investigation will develop an assessment of the general condition with respect to safety of the project based upon available data and a visual inspection, determine any need for emergency measures and conclude if additional studies, investigations and analyses are necessary and warranted." (Chapter 3, Recommended Guidelines for Safety Inspection of Dams).
- c. **Evaluation criteria.** The criteria used to evaluate the dam were established in the "Recommended Guidelines for Safety Inspection of Dams", Engineering Regulation No. 1110-2-106 and Engineering Circular No. 1110-2-188, Engineering and Design National Program for Inspection of Non-Federal Dams prepared by the Office of Chief of Engineers, Department of the Army, and "Hydrologic/Hydraulic Standards, Phase I, Safety Inspection of Non-Federal Dams" prepared by the St Louis District, Corps of Engineers (SLD). These guidelines were developed with the help of several federal agencies and many state agencies, professional engineering organizations, and private engineers.

## 1.2 Description of Project

- a. Description of dam and appurtenances. The Keyes Branch Mine Dam is a tailings dam. The construction of Keyes Branch Mine Dam, as described by Mr Joe Rossier of Milchem, Inc. is somewhat atypical of barite tailings dams in this area. The majority of dams are constructed as a single tier, having a constant slope from crest to toe. The Keyes Branch tiered Dam is a 3 tiered dam. The resulting profile (Fig 3a) is wider and flatter than is typical for tailings dams in this area.

The uppermost tier is constructed of "chat", the gravel-sized waste produced during the milling of the ore (Photo 1). The middle and lower tiers are primarily chat, but have a veneer of "bullrock", large (6 in. to 2 ft) waste rock, placed on the downstream face (Photo 2). This bullrock veneer is quite clayey and may act as an impermeable blanket on the downstream face, allowing seepage pressures to build up behind the face. The flat steps between tiers allow precipitation to enter the dam more readily than on single tier dams.

The material impounded behind the dam consists of silt, sand, and clay produced by washing the barite ore. This fine-grained waste is sluiced into the impoundment where the suspended material is deposited. The resulting sediments are typical of recent lacustrine clay deposits. Where the tailings have been continuously submerged, they have a very soft consistency and high water contents. A stiff crust has formed where the tailings have dried out; however, below the crust the material remains very soft.

The spillway, located at the left abutment, consists of a broad, flat-bottomed notch at the junction of the abutment and dam (Photo 3). The spillway is approximately 70 ft wide at the level of the top of the embankment. The crest of the spillway is approximately 3.2 ft below the elevation of the low point on the top of the embankment. No low level outlet was found. No control structures were found for regulating higher flows.

- b. Location. The dam is located on a tributary of Keyes Branch Creek, approximately 2 mi northeast of the town of Potosi off Missouri Highway E in Washington County, Missouri, Section 6, T37N, R3E, and Section 31, T38N, R3E; see Fig. 1. The dam location is on the USGS Potosi 7.5 minute quadrangle sheet.



- c. **Size classification.** The dam is classified intermediate size based on its 57 ft height and 1400 ac-ft storage capacity.
- d. **Hazard classification.** The St Louis District, Corps of Engineers has classified this dam as a significant hazard dam; we concur with this classification. The estimated damage zone extends approximately 10 mi downstream of the dam. Located within this zone are Missouri State Route E and State Route 47, several crossings of the Missouri-Pacific Railroad, and several gravel roads.
- e. **Ownership.** We understand the dam is owned by Milchem Inc, Mineral Point, Missouri, 63660. Correspondence should be addressed to the attention of Mr Joe Rossier.
- f. **Purpose of dam.** The Keyes Branch Mine Dam was constructed to impound fine barite tailings produced by the washing of barite ore mined in the vicinity. Water impounded by the dam was recycled from the reservoir and used in the barite processing operation.
- g. **Design and construction history.** According to information obtained from Mr Joe Rossier of Milchem, Inc, a starter dam was constructed on the site in 1972. This was further documented in a letter report from the Missouri Geological Survey (Appendix C). A typical cross section of the present configuration of the dam and of the probable configuration of the starter dam is included as Fig. 3a. An engineering design of the starter dam was prepared by Mr Bill Devitt, but consisted of only a general sketch drawing. No provision was made for construction inspection.

The starter dam was constructed of stoney red clay borrowed from the reservoir area and was approximately 30 ft high, 20 ft wide across the crest, with a 5-ft deep cut-off trench.

The main dam was constructed between 1975 and 1979. During this time coarse tailings, ranging from sand to medium gravel size, were dumped along the embankment. The embankment face was stepped upstream to form a

3-tiered embankment. Large rock, to approximately 2 ft diameter, was placed on the downstream face of the lower two tiers. Fine tailings of sand silt and clay size, were sluiced into the impoundment area from the processing plant located on the right abutment.

Mining and processing operations were terminated in December 1979. No work has been done on the dam construction since then, nor is any further work anticipated.

- h. Normal operating procedure. No operating records were found. Overflow passes over the uncontrolled spillway at the left abutment.

### 1.3 Pertinent Data

- a. Drainage area: approximately  $.32 \text{ mi}^2$  (Fig. 2)

- b. Discharge at damsite.

Maximum known flood at damsite	Unknown
Warm water outlet at pool elevation	Not applicable (N/A)
Diversion tunnel low pool outlet at pool elevation	N/A
Diversion tunnel outlet at pool elevation	N/A
Gated spillway capacity at pool elevation	N/A
Gated spillway capacity at maximum pool elevation	N/A
Ungated spillway capacity at maximum pool elevation	$1073 \text{ ft}^3/\text{s}$
Total spillway capacity at maximum pool elevation	$1073 \text{ ft}^3/\text{s}$

- c. Elevation (ft above MSL).

Top of dam	1005.6
Maximum pool - design surcharge	N/A
Full flood control pool	N/A
Recreation pool	N/A
Spillway crest (gated)	N/A
Upstream portal invert diversion tunnel	N/A
Downstream portal invert diversion tunnel	N/A

Streambed at centerline of dam	Unknown
Toe of dam at maximum section	948.7
Maximum tailwater	N/A

d. Reservoir.

Length of maximum pool	Approximately 2000 ft
Length of recreation pool	N/A
Length of flood control pool	N/A

e. Storage (acre-feet)

Recreation pool	N/A
Flood control pool	N/A
Design surcharge	N/A
Top of dam	Approximately 1400 (includes tailings)

f. Reservoir surface (acres).

Top of dam	Approximately 65
Maximum pool	Approximately 65
Flood control pool	N/A
Recreation pool	N/A
Spillway crest	Approximately 60.5

g. Dam.

Type	Tailings
Length	Approximately 1700 ft
Height	56.9 ft (maximum section)
Crest width	Approximately 12 ft (typical)
Side slopes	Downstream 3H to 1V; Upstream unknown
Zoning	Stoney clay starter dam overlain by coarse tailings (see Fig. 3a)
Impervious core	Unknown (probably none)

Cutoff	5-ft deep trench
Grout curtain	Unknown (probably none)

h. Diversion and regulating tunnel.

Type	None
Length	N/A
Closure	N/A
Access	N/A
Regulating Facilities	N/A

i. Spillway.

Type	Unlined notch cut at left abutment
Length of weir	Approximately 70 ft
Crest elevation	1002.4 ft MSL
Gates	None
Upstream channel	None
Downstream channel	Unlined channel through tailings and residual soil

j. Regulating outlets. None

## SECTION 2 ENGINEERING DATA

### 2.1 Design

A general sketch drawing of a starter dam was prepared by Mr Bill Devitt. However, it did not contain specifications on materials or construction inspection. A typical cross section of the starter dam was obtained from the owner's files (Milchem Inc, Potosi, Missouri) and is shown in Fig. 3a.

### 2.2 Construction

The starter dam was constructed in 1972. No records were found of construction inspection of the materials used in the starter dam. A letter report prepared by the Missouri Geological Survey, dated Sept 1975, describing the condition of the dam shortly after barite processing operations began, is presented in Appendix C.

### 2.3 Operation

No operating records were available. Inspection indicates the main dam was constructed of coarse tailings (approximately 3/4 in. maximum particle size) trucked from the processing plant and end-dumped onto the embankment. No records are available on the compaction or actual gradation of the material in the embankment.

Fine tailings mud was carried by flume from the plant on the right abutment, and discharged near the right abutment, at the back of the coarse tailings embankment. A baffle dike composed of coarse tailings extends nearly across the southwestern fourth of the impoundment area. This dike restricts, somewhat, the fine tailings to the northeastern three-fourths of the reservoir and allows the pumping of water for plant operations from the southwestern fourth of the reservoir. See Figure A1, Appendix A for a sketch of the operations layout.

## 2.4 Evaluation

- a. Availability. There are no engineering data available other than the general sketch drawing of the starter dam, and the letter report by the Missouri Geological Survey (Fig. 3a and Appendix C).
- b. Adequacy. The engineering data available is insufficient to evaluate the adequacy of the design of this dam.

Seepage and stability analyses comparable to the requirements of the guidelines are not on record. This is a deficiency which should be rectified. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record. These analyses should be performed by an engineer experienced in the design and construction of dams.

- c. Validity. Not applicable.

## 2.5 Project Geology

The dam site lies on the northern flank of the Ozark structural dome. The regional dip is to the north. The bedrock in the area consists of Cambrian age Eminence and Potosi dolomite formations (Fig. 4). The Potosi Formation is a medium- to fine-grained, light gray dolomite and typically contains an abundance of quartz druse, characteristic of chert bearing formations. The Eminence Formation conformably overlies the Potosi Formation, is similar in appearance but contains less quartz and chert.

The soil at the dam site is a dark red-brown, very sticky, plastic residual clay (CH), characteristically developed on the Potosi Formation. It is locally overlain by a thin (2-5 ft) loess profile of clayey silt (ML). The soils are mapped on the Missouri General Soils Map as Union-Goss-Gasconade-Peridge Association.

The Cabanne Fault, an east-west trending branch of the Big River Fault system, is mapped approximately 2 mi south of the dam. The fault is mapped as north side down and is within the Potosi and Eminence Formations at the surface. The Aptus Fault, a northwest-southeast trending branch of the Big River Fault system is

mapped approximately 4 mi west of the site. The Aptus fault is mapped as southwest side down, and is mapped within the Potosi and Eminence Formations at the surface. The faults are likely Paleozoic in age, and are not considered to be in a seismically active area. The faults are not considered to pose a significant hazard to the dam.

### SECTION 3 VISUAL INSPECTION

#### 3.1 Findings

- a. General. The field inspection was conducted on 15 May 1980; a supplemental inspection was conducted 5 June 1980. These inspections indicated the dam was in a fair to good condition.
- b. Dam. The initial inspection indicated the dam was in good condition. However, on the supplemental visit, a slump-type landslide was noted on the lowest tier of the downstream face of the dam, at approximately station 5+00 to 6+50 measured from the right end of the dam. The slump thickness is apparently less than 5 ft, and the height about 15 to 20 ft. The slide is limited to the "bullrock" slope cover, (6 to 24 in. coarse tailings placed on slope.) Slip on the slide is approximately 5 to 10 ft.

No extensive vegetation is growing on the embankment. No substantial erosion was noted on the face of the embankment. No animal burrows were noted on the face of the embankment.

A moderately large wet area, approximately 50 ft square, with some standing water, was noted at the toe of the dam in the former drainage channel. No single source of seepage, however, could be identified. Total seepage was estimated at approximately 10 gal/min at the time of the inspection. The seepage water was clear and carried no soil.

Some seepage was also noted in the discharge channel downstream from the spillway at the contact between the underlying residual soil and the tailings or waste. This seepage also contributed to minor sloughing along the walls of the discharge channel. The rate of seepage was estimated at less than 1 gal/min at the time of the inspection. The seepage water was clear.



The materials comprising the bulk of the dam consist of coarse tailings or "chat". This material (sandy gravel and gravelly sand, GW-SW) appears quite cohesionless and would likely be severely eroded should the dam be overtopped (Photo 1).

c. Appurtenant structures.

1. Spillway. The spillway at the Keyes Branch Mine Dam consists of a broad, flat-bottomed notch at the left abutment (Photo 3). The floor of the spillway appears to be underlain by residual soil and weathered bedrock. The right side (south side) of the spillway consists of coarse tailings (Fig. 3b).

The highly plastic, stony red clay residual soil and weathered bedrock will likely be slightly to moderately erodible. The tailings portion of the spillway wall will likely be easily eroded during periods of high flow. The flat-bottomed shape of the spillway indicates runoff through the spillway will be in contact with the easily erodible coarse tailings. Erosion of these tailings could lead to undermining of the main dam embankment. Therefore, this portion of the existing spillway may require lining or rip-rap to prevent extensive erosion of the spillway.

- d. Reservoir area. The reservoir area at the time of the inspection was nearly filled with fine tailings carried by flume to the impoundment (Photo 8). The tailings near the discharge end of the flume are quite sandy and are firm enough to walk on. Farther from the flume, the material is quite silty and clayey, water-saturated and very soft. The southwestern part of the reservoir is water covered due to the baffle dike which restricts most of the tailings to the northeastern portion of the impoundment.

The slopes surrounding the reservoir are quite flat, estimated to be less than 5 horizontal to 1 vertical. No indication was found of potentially unstable slopes surrounding the reservoir.

Much of the area around the reservoir is pockmarked with small prospect or development pits 3 to 5 ft in diameter. The majority of these pits have been nearly filled with soil or slopewash debris. They should reduce or delay surface runoff into the reservoir during periods of heavy precipitation.

- e. Downstream channel. The downstream channel below the spillway is a relatively narrow erosion channel, 6 to 8 ft wide at the bottom, cut into residual soil and tailings (Photo 4). These materials appear to be moderately to easily erodible. Seepage occurring at the contact between the tailings and soil has further softened the material and increased its erodibility. The channel walls are approximately 1.5 horizontal to 1 vertical in the tailings, and steeper than 1 horizontal to 1 vertical in the residual soil. High flow through the channel could cause erosion of the walls and result in lateral channel migration downhill toward the toe of the dam. The upper reaches of the channel should be widened and lined or rip-rapped to protect the channel walls from erosion.

### 3.2 Evaluation

The visual inspection of the dam identified a slump type landslide on the downstream face of the dam. This slump occurred in the 3-week interval between the 2 visits to this dam. Although this slump does not appear to pose an immediate hazard to the dam, it did occur where an earlier failure was described by the Missouri Geological Survey (See Appendix C). This record of continued instability suggests additional work is necessary to evaluate the causes of these failures.

The erosion resistance of the spillway and discharge channel appears to be inadequate to carry significant runoff. Substantial erosion could result in migration of the discharge channel and possibly result in erosion at the toe of the dam.

Seepage in the discharge channel and at the toe of the dam did not appear to constitute a hazard to the dam at the time of the inspection. However, the seepage should be monitored to evaluate any increase in discharge or turbidity of the seepage water .

## SECTION 4 OPERATIONAL PROCEDURES

### 4.1 Procedures

Mining operations were begun at the Keyes Branch Mine in early 1975.

Mining and processing operations were discontinued in December 1979. According to Mr Robert Politte, a mine employee at the site, there are no plans to resume operations in the future. The spillway is uncontrolled. No operating procedures currently exist at this structure.

### 4.2 Maintenance of Dam

No maintenance program was available as the facility is inactive and no future activity is planned.

### 4.3 Maintenance of Operating Facilities

Not applicable.

### 4.4 Description of Any Warning System in Effect

As the facility is inactive, no warning system is in effect.

### 4.5 Evaluation

There are no operating facilities or warning procedures in effect at this structure.

There is no known plan for scheduled inspection or monitoring of the dam by the owner in the future. In light of the erodability of the embankment and of portions of the spillway and discharge channel, the condition of the dam and its appurtenant structures may deteriorate with time without being noticed.

## SECTION 5 HYDRAULIC/HYDROLOGIC

### 5.1 Evaluation of Features

- a. Design data. No hydrologic or hydraulic design information was available for evaluation of the dam or the reservoir. Dimensions of the dam and spillway were surveyed 26 May 1980, measured on the date of the visual inspections, or estimated from topographic mapping. The topographic map used was the USGS Potosi 7-1/2 minute quadrangle sheet.
- b. Experience data. No recorded precipitation, runoff, discharge or pool stage data were available for this reservoir or dam. There are no stream gaging stations in the drainage basin.
- c. Visual observations. The spillway constructed at this dam consists of a broad flat weir cut into the left abutment. The soil appears moderately erodible. The erosion potential of the tailings dike adjacent to the spillway is high. On the date of the inspection there were no conditions observed that would indicate a reduced spillway capacity during a flood occurrence. The discharge channel drops steeply and the possibility of supercritical flows in the discharge channel cannot be ruled out.
- d. Overtopping potential. One of the primary considerations in the evaluation of the Keyes Branch Mine Dam is assessment of the potential for overtopping and consequent failure by erosion of the embankment. Since the spillway of this dam is composed of erodible materials, and substantial erosion of the spillway could result in damage to the embankment, the potential consequences of significant spillway discharges are substantially the same as the overtopping of the dam embankment. Hydraulic considerations of the material erodibility and of the spillway geometry suggest that flows below a velocity of 3.5 ft/s or a discharge of less than  $170 \text{ ft}^3/\text{s}$  will not result in substantial spillway erosion. For the purpose of determining the overtopping potential of this dam, spillway discharge of greater than  $170 \text{ ft}^3/\text{s}$  second is considered to produce the effects of overtopping.

Hydrologic analysis of the tailings dam using the data and method as inclosed and described in Appendix B, Hydrology/Hydraulics Data and Analyses, indicate that a flood of greater than 23 percent of the Probable Maximum Flood (PMF) will effectively overtop the dam. The PMF is defined as the flood event that may be expected to occur from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region.

A flood with 1 percent chance of occurrence will be contained within the spillway without overtopping the dam.

The following data were computed for various flood events, assuming no erosion of the spillway or embankment:

Precipitation Event	Maximum Depth of Overtopping ft	Maximum Lake Elevation ft (msl)	Maximum Outflow ft <sup>3</sup> /s	Duration of Overtop hr
10% Prob	0	1002.9	50	0
1% Prob	0	1003.2	90	0
23% PMF	0	1003.6 (effective top of dam)	165	0
50% PMF	0	1004.6	490	0
100% PMF	0.4	1006.0	1360	1.3

## SECTION 6 STRUCTURAL STABILITY

### 6.1 Evaluation of Structural Stability

- a. Visual observations. The field inspection identified a slump-type slide on the south end of the downstream face of the dam embankment. The slide appears to be limited to the coarse rock layer placed as slope erosion protection (2- to 5-ft thick) and does not appear to constitute an immediate hazard to the stability of the dam.

A letter report dated September 23, 1975, by the Missouri Geological Survey (Appendix C), describes a backslope rotational slide which also occurred at the south end of the dam. This slide occurred shortly after barite mining operations had begun. Fine tailings mud had not been deposited along the entire length of the starter dam and leakage was described as high along the entire length of the dam. Slime resembling barite mud was observed for some 500 ft in the stream channel below the dam. There was evidence that water had percolated through the starter dam and transported some fine material downstream. The report recommended that material pushed onto the slide be removed; the toe of the dam be buttressed by a free draining berm of rock; and that mud be spread by flume along the entire crest of the dam to aid in sealing the gravel. There is no report describing whether these recommendations were carried out. However, there was no evidence of significant seepage or barite slimes downstream during the visual inspection recently completed.

The seepage noted at the toe of the dam at the time of the inspection did not appear to pose a hazard to the stability of the dam.

The spillway and discharge channel are judged to be in poor condition due to the potential for erosion during periods of high flow. Seepage in the discharge channel has softened the material and probably increased the erodibility of

the soil. Lateral and headward erosion of the discharge channel could result in erosion of the toe of the dam or the spillway and reduce the structural stability of the embankment.

- b. Design and construction data. No design or construction data relating to structural stability were found.
- c. Operating records. No appurtenant structures requiring operation exist at this dam. Seepage and stability analyses comparable to the requirements of the guidelines are not on record. This is a deficiency which should be corrected to meet the recommended guidelines.
- d. Post construction changes. Based on aerial photo interpretation of the site area, the most significant post construction change in the vicinity of the dam is the land clearing and mining operations which have been conducted on the slopes around the reservoir area. This will likely increase the runoff and siltation below the cleared and mined areas. Much of the mined area, however, drains into Keyes Branch Creek below the dam. No other significant post construction changes are known or apparent.
- e. Seismic stability. The dam is located in Seismic Zone 2, to which the guidelines assign a moderate damage potential. Since no static stability analysis of the dam is available for review, the seismic stability cannot be evaluated. However, the saturated and very soft condition of the tailings in the reservoir and the granular nature of the dam suggest substantial damage or failure could occur in the event of a severe seismic event.

## SECTION 7 ASSESSMENT/REMEDIAL MEASURES

### 7.1 Dam Assessment

- a. **Safety.** Based on the visual inspection, the Keyes Branch Dam appears to be in fair to good condition. The effect of the observed slide on the stability of the dam needs to be evaluated. The erosion potential of the dam, if overtopped, and the erodibility of the spillway and discharge channel are deficiencies which should be corrected to increase the long term stability of the dam.
- b. **Adequacy of information.** The lack of stability and seepage analyses for the dam as recommended in the guidelines precludes an evaluation of the structural and seismic stability of the dam. The lack of these analyses is a deficiency which should be rectified to meet the recommended guidelines.
- c. **Urgency.** The deficiencies described in this report could affect the safety of the dam. Corrective actions should be initiated promptly.
- d. **Necessity for Phase II.** In accordance with the Recommended Guidelines for Safety Inspections of Dams, the subject investigation was a minimum study. This study revealed that additional in-depth investigations are needed to complete the assessment of the safety of the dam. Those investigations which should be performed without undue delay are described in Section 7.2b. It is our understanding from discussions with the St Louis District that any additional investigations are the responsibility of the owner.

### 7.2 Remedial Measures

- a. **Alternatives.** There are several general options which may be considered to reduce the possibility of dam failure. Some of these options are:
  1. Remove the dam, or breach it to prevent storage of water.



2. Increase the height of dam and/or spillway size to pass the probable maximum flood without overtopping the dam.
  3. Purchase downstream land that would be adversely impacted by dam failure and restrict human occupancy.
  4. Enhance the stability of the dam to permit overtopping by the probable maximum flood without failure.
  5. Provide a highly reliable flood warning system (generally does not prevent damage but avoids loss of life).
- b. **Recommendations.** Based on our inspection of the Keyes Branch Mine Dam, it is recommended that further study be conducted without undue delay under the guidance of an engineer experienced in design and construction of dams to evaluate, as a minimum, the following topics:
1. What spillway capacity should be provided, and in what manner, taking into consideration the high potential erodibility of the embankment materials in the event of overtopping.
  2. Potential for erosion during period of heavy flow within the spillway and adjacent portion of the embankment, including erosion mitigating options.
  3. Potential for erosion and lateral migration in the discharge channel, including erosion mitigating options.
- c. **Operation and maintenance procedures.** In view of the discontinued operations at this site and the erodibility of the spillway and discharge channel, the potential for deterioration of the stability of the dam indicates a program of periodic inspections should be designed and implemented for this facility. Any deterioration of the dam conditions should be called to the attention of an engineer experienced in design and construction of dams. This program should include:


1. A monitoring program to periodically check the condition of the face of the dam, with special regard to the south end where small slope failure has been noted in the past and at present.
2. Monitor seepage to identify changes in the amount of seepage flow or turbidity (soil) in the seepage water.
3. Inspect the spillway and discharge channel for evidence of substantial erosion which could pose a hazard to the embankment stability.

## REFERENCES


- Allgood, Ferris P., and Persinger, Ivan, D., 1979, "Missouri General Soil Map and Soil Association Descriptions," US Department of Agriculture, Soil Conservation Service and Missouri Agricultural Experiment Station.
- Department of the Army, Office of the Chief of Engineers, 1977, EC 1110-2-188, "National Program of Inspection of Non-Federal Dams".
- Department of the Army, Office of the Chief of Engineers, 1979, ER 1110-2-106, "National Program of Inspection of Non-Federal Dams".
- Hydrologic Engineering Center, US Army Corps of Engineers, 1978, "Flood Hydrograph Package (HEC-1) Users Manual for Dam Safety Investigations".
- McCracken, Mary H., 1971, Structural Features Map of Missouri: Missouri Geological Survey, Scale 1:500,000.
- Missouri Geological Survey, 1979, Geologic Map of Missouri: Missouri Geological Survey, Scale 1:500,000.
- St Louis District, US Army Corps of Engineers, 1979, "Hydrologic/Hydraulic Standards, Phase I Safety Inspection of Non-Federal Dams".
- US Department of Commerce, US Weather Bureau, 1956, "Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1,000 Square Miles and Durations of 6, 12, 24 and 48 Hours," Hydrometeorological Report No. 33.
- US Soil Conservation Service, 1971, "National Engineering Handbook," Section 4, Hydrology, 1971.








SECTION A-A  
MAXIMUM CROSS SECTION (STA



PLAN  
SURVEYED ELEVATION OF DAM CREST,  
KEYES BRANCH MINE DAM

Downstream




Notes:

1. Information on starter dam provided by Mr Joe Rossier, Milchem Inc.
  - Location within main dam as shown
  - Max height 30 ft
  - Width at base: 150 ft (typ)
  - Constructed of Clayey soil borrowed from pond area
  - Compaction by construction equipment
  - No drains
2. No chimney or blanket drain
3. See Fig. 2 Appendix 2, for spillway plan and cross-sections
4. Existing dam profile from survey 26 May 1980

SECTION A-A

SECTION (STA 7+52.5) LOOKING NORTH



**CROSS-SECTION  
AND SURVEYED  
CREST ELEVATIONS**


KEYES BRANCH MINE DAM

MO. 30386

Fig. 3a

CREST,


2



Elev. ft (MSL)  
100  
100  
99

PLAN OF SPILLWAY





# **CROSS-SECTION AND PLAN OF SPILLWAY**

KEYES BRANCH MINE DAM

MO. 30386

Fig. 36


# DAM LOCATION




## Legend



Roubidoux Formation



Gasconade Dolomite  
Gunter Sandstone Member



Eminence Dolomite



Potosi Dolomite



Derby-Doerun Dolomite



Davis Formation



Bonneterre Formation  
Whetstone Creek Member  
Sullivan Siltstone Member



Reagan Sandstone  
(subsurface, western Missouri)



Lamotte Sandstone




Diabase (dikes and sills)



St. Francois Mountains Intrusive Suite



St. Francois Mountains Volcanic Supergroup



## REGIONAL GEOLOGIC MAP


KEYES BRANCH MINE DAM

MO 30386

FIG 4

## **APPENDIX A**

### **Photographs**



# PHOTO LOCATION SKETCH

KEYES BRANCH MINE DAM

MO. 30386

Fig. A-1



1. Downstream face of dam looking North toward spillway



2. Rock cover on face of dam looking South

NOTE: Marshy area at toe of dam.



3. Spillway at left abutment, looking upstream.



4. Eroded discharge channel below spillway looking downstream.



5. Erosion downstream on discharge channel looking West, upstream.



6. View of area downstream of dam, looking West. Dam in background.



7. Discharge flume from processing plant looking Northeast toward Dam.



8. Filled reservoir area looking North-Northeast from processing plant.





9. Shallow slope failure on lowest tier of downstream face of dam. Looking north.



10. Head scarp of slope failure on downstream face of dam. Note failure consists predominantly of bullrock slope cover. Looking south.

## **APPENDIX B**

### **Hydraulic/Hydrologic Data and Analyses**

## APPENDIX B

### Hydraulic/Hydrologic Analyses

#### B.1 Procedures

- a. **General.** The hydraulic/hydrologic analyses were performed using the "HEC-1, Dam Safety Version (1 Apr 80)" computer program. Inflow hydrographs were developed by applying various precipitation events to a synthetic unit hydrographs. The inflow hydrographs, thus obtained, were then routed through the reservoir and appurtenant structures by the modified Puls reservoir routing method used in the HEC-1 program to determine overtopping potential.
- b. **Precipitation events.** Various percentages including 100 percent of the Probable Maximum Precipitation (PMP) and the 1 and 10 percent probability-of-occurrence events were used in the analyses. The PMP was determined from regional charts prepared by the US Weather Bureau (1956). The 1 and 10 percent probability-of-occurrence events were provided by SLD.
- c. **Unit hydrograph.** The Soil Conservation Service (SCS) unit hydrograph (SCS, 1971) for a storm duration of 48 hrs was used to develop the inflow hydrograph. The unit hydrograph was divided into 10 min increments.
- d. **Infiltration losses.** The SCS curve number (CN) method was used to compute infiltration losses. Curve numbers were selected on the basis of antecedent moisture conditions in accordance with the guidelines, present land usage and hydrologic soil group of the soils in the drainage basin. Where more than one soil group was present, the group giving the highest CN was used for the entire basin. If the soil group was not available, group D was assumed.
- e. **Lag time.** Lag time was computed by the SCS method (SCS, 1971).

#### B.2 Pertinent Data

- a. **Drainage area:** 0.32 mi<sup>2</sup>
- b. **Lag time:** - 0.34 hrs
- c. **Hydrologic soil group:** C
- d. **SCS curve numbers.**
  1. For PMF: 87 (AMC III)
  2. For 1 and 10 percent probability-of-occurrence events: 73 (AMCII)

- e. **Storage.** Elevation-area data were developed by planimetering areas at various elevation contours on the USGS Potosi 7.5-minute quadrangle map. The data were entered on the \$A and \$E cards so that the HEC-1 program could compute storage volumes.
- f. **Outflow capacity.** The elevation-discharge relationship was developed from cross-sections of the spillway and downstream channel using the HEC-2 backwater profile program and entered on the Y4 and Y5 cards for the HEC-1 program.
- g. **Outflow over crest.** As the profile of the dam crest is irregular, flow over the crest cannot be determined by conventional weir formulas. Crest length-elevation data and hydraulic constants for the crest were entered on \$D, \$L and \$V cards.
- h. **Reservoir elevations.** For all fractions of the PMF, the starting reservoir elevation was the spillway crest elevation of 1002.4 ft. For the 1 and 10 percent probability-of-occurrence events, the starting reservoir elevation was 1002.4 ft, the elevation of the high water line in the reservoir area.

### **B.3 Results**

The results of the analyses, as well as the input values to the HEC-1 program, follow in this Appendix. Only the results summaries are included, not the intermediate output. Complete copies of the HEC-1 output are available in the project file.



\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DATA ENTRY VERSION JULY 1978  
 LAST MODIFICATION 01 APR 80  
 \*\*\*\*\*

RUN DATE: 31 JUL 80  
 TIME: 10.31.53

KEYES BRANCH TRAILINGS DIV NO. 30386, WASHINGTON COUNTY, MISSOURI.  
 WOODWARD-CLOYE CONSULTANTS, HOUSTON JOB 70H009.  
 PROBABLE MAXIMUM FLOODS (PMF) ANALYSIS

JOB SPECIFICATION									
NO	NHR	MMH	IDAY	IHR	IMH	METC	IPLT	IPRT	MSAN
208	0	3	-0	-0	-0	-0	-0	-0	-0
JOPEZ		5	-0	-0	-0	-0	TRACE		

MULTI-PLAN ANALYSES TO BE PERFORMED

PLAN 1: RATIO = 1.00

RTIOS = .25 .50 .75 1.00

SUB-AREA RUNOFF COMPUTATION

KEYES BRANCH DIV NO. 30386, WASHINGTON COUNTY, MISSOURI.

ISTAD	ICOMP	TECOM	ITAPE	JPLT	JPRY	I4AME	ISAGE	IAUTO
1	2	32	-0	-0	-0	1	-0	-0

HYDROGRAPH DATA

TIME	PRECIP	Q5	Q12	Q24	Q48	Q72	Q96
1	32	-0	120.00	130.00	-0	-0	-0

LOSS DATA

LEOPT	STRK	OLTR	RTIOL	ERAIN	STKRS	RTIOL	STREL	CHSTL	ALSMX	RTIMP
0	0	0	1.00	-0	-0	1.00	-1.00	-0.00	-0	.22

CURVE NO = -07.00 WETNESS = -1.00 EFFECT CN = 07.00

UNIT HYDROGRAPH DATA

FC = -0. LAG = .34

RECESSION DATA

STRAT = -10.00 DRCSN = -.10 RTIOL = 2.00

UNIT HYDROGRAPH 22 END OF PERIOD ORIGINATES, FC = -0. HOURS, LAG = .34 VOL = 1.00

Q7	Q10	Q15	Q20	Q25	Q30	Q35	Q40	Q45	Q50	Q55	Q60	Q65	Q70	Q75	Q80	Q85	Q90	Q95	Q100
149	303	394	401	345	261	173	120	86											

Input Data  
 Various PMF Events  
 Keyes Branch Mine Dam  
 MO 30386

1.01	1.00	1	.01	.00	.01	.01	1.	1.01	12.05	145	.22	.21	.01	167.
1.01	1.00	2	.01	.00	.01	.01	3.	1.01	12.10	146	.22	.21	.01	164.
1.01	1.01	3	.01	.00	.01	.01	4.	1.01	12.15	147	.22	.21	.01	230.
1.01	1.01	4	.01	.00	.01	.01	5.	1.01	12.20	148	.22	.21	.01	290.
1.01	1.01	5	.01	.00	.01	.01	6.	1.01	12.25	149	.22	.21	.01	351.
1.01	1.01	6	.01	.00	.01	.01	7.	1.01	12.30	150	.22	.22	.01	403.
1.01	1.01	7	.01	.00	.01	.01	8.	1.01	12.35	151	.22	.22	.01	443.
1.01	1.01	8	.01	.00	.01	.01	9.	1.01	12.40	152	.22	.22	.01	470.
1.01	1.01	9	.01	.00	.01	.01	7.	1.01	12.45	153	.22	.22	.00	480.
1.01	1.01	10	.01	.00	.01	.01	9.	1.01	12.50	154	.22	.22	.00	502.
1.01	1.01	11	.01	.00	.01	.01	9.	1.01	12.55	155	.22	.22	.00	512.
1.01	1.01	12	.01	.00	.01	.01	9.	1.01	13.00	156	.22	.22	.00	519.
1.01	1.01	13	.01	.00	.01	.01	9.	1.01	13.05	157	.22	.22	.00	526.
1.01	1.01	14	.01	.00	.01	.01	9.	1.01	13.10	158	.22	.22	.00	537.
1.01	1.01	15	.01	.00	.01	.01	9.	1.01	13.15	159	.22	.22	.00	552.
1.01	1.01	16	.01	.00	.01	.01	9.	1.01	13.20	160	.22	.22	.00	572.
1.01	1.01	17	.01	.00	.01	.01	9.	1.01	13.25	161	.22	.22	.00	591.
1.01	1.01	18	.01	.00	.01	.01	9.	1.01	13.30	162	.22	.22	.00	607.
1.01	1.01	19	.01	.00	.01	.01	9.	1.01	13.35	163	.22	.22	.00	620.
1.01	1.01	20	.01	.00	.01	.01	9.	1.01	13.40	164	.22	.22	.00	628.
1.01	1.01	21	.01	.00	.01	.01	9.	1.01	13.45	165	.22	.22	.00	634.
1.01	1.01	22	.01	.00	.01	.01	9.	1.01	13.50	166	.22	.22	.00	638.
1.01	1.01	23	.01	.00	.01	.01	9.	1.01	13.55	167	.22	.22	.00	641.
1.01	1.01	24	.01	.00	.01	.01	9.	1.01	14.00	168	.22	.22	.00	644.
1.01	1.01	25	.01	.00	.01	.01	9.	1.01	14.05	169	.22	.22	.00	649.
1.01	1.01	26	.01	.00	.01	.01	9.	1.01	14.10	170	.22	.22	.00	659.
1.01	1.01	27	.01	.00	.01	.01	9.	1.01	14.15	171	.22	.22	.00	680.
1.01	1.01	28	.01	.00	.01	.01	10.	1.01	14.20	172	.22	.22	.00	707.
1.01	1.01	29	.01	.00	.01	.01	10.	1.01	14.25	173	.22	.22	.00	735.
1.01	1.01	30	.01	.00	.01	.01	10.	1.01	14.30	174	.22	.22	.00	757.
1.01	1.01	31	.01	.00	.01	.01	11.	1.01	14.35	175	.22	.22	.00	775.
1.01	1.01	32	.01	.00	.01	.01	11.	1.01	14.40	176	.22	.22	.00	787.
1.01	1.01	33	.01	.00	.01	.01	12.	1.01	14.45	177	.22	.22	.00	795.
1.01	1.01	34	.01	.00	.01	.01	12.	1.01	14.50	178	.22	.22	.00	801.
1.01	1.01	35	.01	.00	.01	.01	12.	1.01	14.55	179	.22	.22	.00	805.
1.01	1.01	36	.01	.00	.01	.01	13.	1.01	15.00	180	.22	.22	.00	809.
1.01	1.01	37	.01	.00	.01	.01	13.	1.01	15.05	181	.22	.22	.00	805.
1.01	1.01	38	.01	.00	.01	.01	14.	1.01	15.10	182	.22	.22	.00	796.
1.01	1.01	39	.01	.00	.01	.01	14.	1.01	15.15	183	.22	.22	.00	788.
1.01	1.01	40	.01	.00	.01	.01	14.	1.01	15.20	184	.22	.22	.00	808.
1.01	1.01	41	.01	.00	.01	.01	15.	1.01	15.25	185	.22	.22	.00	871.
1.01	1.01	42	.01	.00	.01	.01	15.	1.01	15.30	186	.22	.22	.01	1030.
1.01	1.01	43	.01	.00	.01	.01	15.	1.01	15.35	187	.22	.22	.01	1377.
1.01	1.01	44	.01	.00	.01	.01	16.	1.01	15.40	188	.22	.22	.01	1416.
1.01	1.01	45	.01	.00	.01	.01	16.	1.01	15.45	189	.22	.22	.00	2501.
1.01	1.01	46	.01	.00	.01	.01	16.	1.01	15.50	190	.22	.22	.00	2859.
1.01	1.01	47	.01	.00	.01	.01	17.	1.01	15.55	191	.22	.22	.00	2900.
1.01	1.01	48	.01	.00	.01	.01	17.	1.01	16.00	192	.22	.22	.00	2689.
1.01	1.01	49	.01	.00	.01	.01	17.	1.01	16.05	193	.22	.22	.00	2311.
1.01	1.01	50	.01	.00	.01	.01	17.	1.01	16.10	194	.22	.22	.00	1949.
1.01	1.01	51	.01	.00	.01	.01	18.	1.01	16.15	195	.22	.22	.00	1642.
1.01	1.01	52	.01	.00	.01	.01	18.	1.01	16.20	196	.22	.22	.00	1402.
1.01	1.01	53	.01	.00	.01	.01	18.	1.01	16.25	197	.22	.22	.00	1219.
1.01	1.01	54	.01	.00	.01	.01	19.	1.01	16.30	198	.22	.22	.00	1082.
1.01	1.01	55	.01	.00	.01	.01	19.	1.01	16.35	199	.22	.22	.00	985.
1.01	1.01	56	.01	.00	.01	.01	19.	1.01	16.40	200	.22	.22	.00	920.
1.01	1.01	57	.01	.00	.01	.01	19.	1.01	16.45	201	.22	.22	.00	874.
1.01	1.01	58	.01	.00	.01	.01	20.	1.01	16.50	202	.22	.22	.00	841.
1.01	1.01	59	.01	.00	.01	.01	20.	1.01	16.55	203	.22	.22	.00	819.
1.01	1.01	60	.01	.00	.01	.01	20.	1.01	17.00	204	.22	.22	.00	803.
1.01	1.01	61	.01	.00	.01	.01	20.	1.01	17.05	205	.22	.22	.00	789.

Input Data  
Various PMF Events  
Branch Mine Data  
1082.MO 30386

1.01	5.30	66	.01	.01	.01	.01	.01	1.01	17.25	234	.24	.24	.00	642.
1.01	5.35	67	.01	.01	.01	.01	.01	1.01	17.30	210	.24	.24	.00	658.
1.01	5.40	68	.01	.01	.01	.01	.01	1.01	17.35	211	.24	.24	.00	640.
1.01	5.45	69	.01	.01	.01	.01	.01	1.01	17.40	212	.24	.24	.00	628.
1.01	5.50	70	.01	.01	.01	.01	.01	1.01	17.45	213	.24	.24	.00	670.
1.01	5.55	71	.01	.01	.01	.01	.01	1.01	17.50	214	.24	.24	.00	614.
1.01	5.60	72	.01	.01	.01	.01	.01	1.01	17.55	215	.24	.24	.00	619.
1.01	5.65	73	.01	.01	.01	.01	.01	1.01	18.00	216	.24	.24	.00	607.
1.01	5.70	74	.01	.01	.01	.01	.01	1.01	18.05	217	.02	.02	.00	599.
1.01	5.75	75	.01	.01	.01	.01	.01	1.01	18.10	218	.02	.02	.00	561.
1.01	5.80	76	.01	.01	.01	.01	.01	1.01	18.15	219	.02	.02	.00	493.
1.01	5.85	77	.01	.01	.01	.01	.01	1.01	18.20	220	.02	.02	.00	409.
1.01	5.90	78	.01	.01	.01	.01	.01	1.01	18.25	221	.02	.02	.00	315.
1.01	5.95	79	.01	.01	.01	.01	.01	1.01	18.30	222	.02	.02	.00	277.
1.01	6.00	80	.01	.01	.01	.01	.01	1.01	18.35	223	.02	.02	.00	294.
1.01	6.05	81	.01	.01	.01	.01	.01	1.01	18.40	224	.02	.02	.00	241.
1.01	6.10	82	.01	.01	.01	.01	.01	1.01	18.45	225	.02	.02	.00	225.
1.01	6.15	83	.01	.01	.01	.01	.01	1.01	18.50	226	.02	.02	.00	210.
1.01	6.20	84	.01	.01	.01	.01	.01	1.01	18.55	227	.02	.02	.00	196.
1.01	6.25	85	.01	.01	.01	.01	.01	1.01	19.00	228	.02	.02	.00	183.
1.01	6.30	86	.01	.01	.01	.01	.01	1.01	19.05	229	.02	.02	.00	171.
1.01	6.35	87	.01	.01	.01	.01	.01	1.01	19.10	230	.02	.02	.00	159.
1.01	6.40	88	.01	.01	.01	.01	.01	1.01	19.15	231	.02	.02	.00	149.
1.01	6.45	89	.01	.01	.01	.01	.01	1.01	19.20	232	.02	.02	.00	139.
1.01	6.50	90	.01	.01	.01	.01	.01	1.01	19.25	233	.02	.02	.00	129.
1.01	6.55	91	.01	.01	.01	.01	.01	1.01	19.30	234	.02	.02	.00	121.
1.01	6.60	92	.01	.01	.01	.01	.01	1.01	19.35	235	.02	.02	.00	113.
1.01	6.65	93	.01	.01	.01	.01	.01	1.01	19.40	236	.02	.02	.00	105.
1.01	6.70	94	.01	.01	.01	.01	.01	1.01	19.45	237	.02	.02	.00	98.
1.01	6.75	95	.01	.01	.01	.01	.01	1.01	19.50	238	.02	.02	.00	91.
1.01	6.80	96	.01	.01	.01	.01	.01	1.01	19.55	239	.02	.02	.00	84.
1.01	6.85	97	.01	.01	.01	.01	.01	1.01	20.00	240	.02	.02	.00	80.
1.01	6.90	98	.01	.01	.01	.01	.01	1.01	20.05	241	.02	.02	.00	74.
1.01	6.95	99	.01	.01	.01	.01	.01	1.01	20.10	242	.02	.02	.00	69.
1.01	7.00	100	.01	.01	.01	.01	.01	1.01	20.15	243	.02	.02	.00	65.
1.01	7.05	101	.01	.01	.01	.01	.01	1.01	20.20	244	.02	.02	.00	60.
1.01	7.10	102	.01	.01	.01	.01	.01	1.01	20.25	245	.02	.02	.00	56.
1.01	7.15	103	.01	.01	.01	.01	.01	1.01	20.30	246	.02	.02	.00	54.
1.01	7.20	104	.01	.01	.01	.01	.01	1.01	20.35	247	.02	.02	.00	52.
1.01	7.25	105	.01	.01	.01	.01	.01	1.01	20.40	248	.02	.02	.00	50.
1.01	7.30	106	.01	.01	.01	.01	.01	1.01	20.45	249	.02	.02	.00	55.
1.01	7.35	107	.01	.01	.01	.01	.01	1.01	20.50	250	.02	.02	.00	54.
1.01	7.40	108	.01	.01	.01	.01	.01	1.01	20.55	251	.02	.02	.00	54.
1.01	7.45	109	.01	.01	.01	.01	.01	1.01	21.00	252	.02	.02	.00	54.
1.01	7.50	110	.01	.01	.01	.01	.01	1.01	21.05	253	.02	.02	.00	54.
1.01	7.55	111	.01	.01	.01	.01	.01	1.01	21.10	254	.02	.02	.00	54.
1.01	7.60	112	.01	.01	.01	.01	.01	1.01	21.15	255	.02	.02	.00	54.
1.01	7.65	113	.01	.01	.01	.01	.01	1.01	21.20	256	.02	.02	.00	54.
1.01	7.70	114	.01	.01	.01	.01	.01	1.01	21.25	257	.02	.02	.00	54.
1.01	7.75	115	.01	.01	.01	.01	.01	1.01	21.30	258	.02	.02	.00	54.
1.01	7.80	116	.01	.01	.01	.01	.01	1.01	21.35	259	.02	.02	.00	54.
1.01	7.85	117	.01	.01	.01	.01	.01	1.01	21.40	260	.02	.02	.00	54.
1.01	7.90	118	.01	.01	.01	.01	.01	1.01	21.45	261	.02	.02	.00	54.
1.01	7.95	119	.01	.01	.01	.01	.01	1.01	21.50	262	.02	.02	.00	54.
1.01	8.00	120	.01	.01	.01	.01	.01	1.01	21.55	263	.02	.02	.00	54.
1.01	8.05	121	.01	.01	.01	.01	.01	1.01	22.00	264	.02	.02	.00	54.
1.01	8.10	122	.01	.01	.01	.01	.01	1.01	22.05	265	.02	.02	.00	54.
1.01	8.15	123	.01	.01	.01	.01	.01	1.01	22.10	266	.02	.02	.00	54.
1.01	8.20	124	.01	.01	.01	.01	.01	1.01	22.15	267	.02	.02	.00	54.
1.01	8.25	125	.01	.01	.01	.01	.01	1.01	22.20	268	.02	.02	.00	54.
1.01	8.30	126	.01	.01	.01	.01	.01	1.01	22.25	269	.02	.02	.00	54.
1.01	8.35	127	.01	.01	.01	.01	.01	1.01	22.30	270	.02	.02	.00	54.
1.01	8.40	128	.01	.01	.01	.01	.01	1.01	22.35	271	.02	.02	.00	54.
1.01	8.45	129	.01	.01	.01	.01	.01	1.01	22.40	272	.02	.02	.00	54.
1.01	8.50	130	.01	.01	.01	.01	.01	1.01	22.45	273	.02	.02	.00	54.
1.01	8.55	131	.01	.01	.01	.01	.01	1.01	22.50	274	.02	.02	.00	54.
1.01	8.60	132	.01	.01	.01	.01	.01	1.01	22.55	275	.02	.02	.00	54.
1.01	8.65	133	.01	.01	.01	.01	.01	1.01	22.60	276	.02	.02	.00	54.
1.01	8.70	134	.01	.01	.01	.01	.01	1.01	22.65	277	.02	.02	.00	54.
1.01	8.75	135	.01	.01	.01	.01	.01	1.01	22.70	278	.02	.02	.00	54.
1.01	8.80	136	.01	.01	.01	.01	.01	1.01	22.75	279	.02	.02	.00	54.
1.01	8.85	137	.01	.01	.01	.01	.01	1.01	22.80	280	.02	.02	.00	54.
1.01	8.90	138	.01	.01	.01	.01	.01	1.01	22.85	281	.02	.02	.00	54.
1.01	8.95	139	.01	.01	.01	.01	.01	1.01	22.90	282	.02	.02	.00	54.
1.01	9.00	140	.01	.01	.01	.01	.01	1.01	22.95	283	.02	.02	.00	54.
1.01	9.05	141	.01	.01	.01	.01	.01	1.01	23.00	284	.02	.02	.00	54.
1.01	9.10	142	.01	.01	.01	.01	.01	1.01	23.05	285	.02	.02	.00	54.
1.01	9.15	143	.01	.01	.01	.01	.01	1.01	23.10	286	.02	.02	.00	54.
1.01	9.20	144	.01	.01	.01	.01	.01	1.01	23.15	287	.02	.02	.00	54.
1.01	9.25	145	.01	.01	.01	.01	.01	1.01	23.20	288	.02	.02	.00	54.
1.01	9.30	146	.01	.01	.01	.01	.01	1.01	23.25	289	.02	.02	.00	54.
1.01	9.35	147	.01	.01	.01	.01	.01	1.01	23.30	290	.02	.02	.00	54.
1.01	9.40	148	.01	.01	.01	.01	.01	1.01	23.35	291	.02	.02	.00	54.
1.01	9.45	149	.01	.01	.01	.01	.01	1.01	23.40	292	.02	.02	.00	54.
1.01	9.50	150	.01	.01	.01	.01	.01	1.01	23.45	293	.02	.02	.00	54.
1.01	9.55	151	.01	.01	.01	.01	.01	1.01	23.50	294	.02	.02	.00	54.
1.01	9.60	152	.01	.01	.01	.01	.01	1.01	23.55	295	.02	.02	.00	54.
1.01	9.65	153	.01	.01	.01	.01	.01	1.01	23.60	296	.02	.02	.00	54.
1.01	9.70	154	.01	.01	.01	.01	.01	1.01	23.65	297	.02	.02	.00	54.
1.01	9.75	155	.01	.01	.01	.01	.01	1.01	23.70	298	.02	.02	.00	54.
1.01	9.80	156	.01	.01	.01	.01	.01	1.01	23.75	299	.02	.02	.00	54.
1.01	9.85	157	.01	.01	.01	.01	.01	1.01	23.80	300	.02	.02	.00	54.
1.01	9.90	158	.01	.01	.01	.01	.01	1.01	23.85	301	.02	.02	.00	54.
1.01	9.95	159	.01	.01	.01	.01	.01	1.01	23.90	302	.02	.02	.00	54.
1.01	10.00	160	.01	.01	.01	.01	.01	1.01	23.95	303	.02	.02	.00	54.
1.01	10.05	161	.01	.01	.01	.01	.01	1.01	24.00	304	.02	.02	.00	54.
1.01	10.10	162	.01	.01	.01	.01	.01	1.01	24.05	305	.02	.02	.00	54.
1.01	10.15	163	.01	.01	.01	.01	.01	1.01	24.10	306	.02	.02	.00	54.
1.01	10.20	164	.01	.01	.01	.01	.01	1.01	24.15	307	.02	.02	.00	54.
1.01	10.25	165	.01	.01	.01	.01	.01	1.01	24.20	308	.02	.02	.00	54.
1.01	10.30	166	.01	.01	.01	.01	.01	1.01	24.25	309	.02	.02	.00	54.
1.01	10.35	167	.01	.01	.01	.01	.01	1.01	24.30	310	.02	.02	.00	54.
1.01														





PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

RATIOS APPLIED TO FLOWS

OPERATION	STATION	AREA	PLAN	RATIO 1	RATIO 2	RATIO 3	RATIO 4
				.25	.50	.75	1.00

HYDROGRAPH AT	INFLW	.32	1	725.	1450.	2175.	2900.
		.037		20.337	41.087	61.397	82.127

ROUTED TO	DAM	.32	1	145.	490.	893.	1358.
		.037		3.637	12.867	23.307	36.447

Output Summary  
 Various PMF Events  
 Keys Branch Mine Dam  
 MO 30386

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....		ELEVATION	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM		
			1002.40	1002.40	1005.60		
		STORAGE	1192.	1192.	1395.		
		OUTFLOW	0.	0.	1075.		
RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER JAW	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.25	1003.68	0.	1271.	195.	0.	17.25	0.
.50	1004.99	0.	1329.	290.	0.	16.58	0.
.75	1005.34	0.	1377.	893.	0.	16.42	0.
1.00	1005.96	.36	1418.	1358.	1.33	16.33	0.

Output Summary  
Various PMF Events  
Keys Branch Mine Dam  
MO 30386

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1	ELEVATION	INITIAL VALUE	SPELLWAY CREST	TOP OF DAM
	STORAGE	1002.40	1002.40	1003.60
	OUTFLOW	0.	0.	167.

RATIO OF PMF	MAXIMUM RESERVOIR ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.22	1003.55	0.	1263.	156.	0.	17.33	0.
.23	1003.59	0.	1265.	162.	0.	17.33	0.
.24	1003.63	.03	1268.	175.	1.83	17.25	0.
.25	1003.60	.08	1271.	185.	2.33	17.25	0.

PMF Over Topping  
Analysis, Assuming Erosion  
Of Spillway at + 170 cfs  
Discharge.  
Keys Branch Mine Dam  
MO 30386

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....		ELEVATION	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
.. ..		1005.60	1002.40	1002.40	1005.60
STORAGE		1192.	1192.	1192.	1395.
OUTFLOW		0.	0.	0.	1975.
RATIO OF	MAXIMUM	MAXIMUM	MAXIMUM	DURATION	TIME OF
PMF	RESERVOIR	DEPTH	STORAGE	OVER TOP	FAILURE
	WCS-ELEV	OVER DAM	AC-FT	HOURS	HOURS
.85	1005.60	0.	1395.	0.	16.42
.90	1005.72	.12	1403.	.67	16.42
.95	1005.84	.24	1411.	1.00	16.33
1.00	1005.96	.36	1418.	1.33	16.33

PMF Over Topping  
Analysis. Assuming  
No Spillway Erosion  
Keys Branch Mine Dam  
MO 30386

## **APPENDIX C**

**Letter Report on Melchem-Keyes Branch Tailings  
Pond From Missouri Geological Survey**

ENGINEERING GEOLOGIC REPORT ON THE MILCHEM-KEYES BRANCH-TAILINGS POND

Washington County, Mo.

LOCATION: NW $\frac{1}{4}$ , Sec. 6, T. 37 N., R. 3 E., Potosi Quadrangle.

The tailings pond is underlain by Potosi dolomite. However, bedrock is not exposed within the region. The starter dam is constructed of stony red clay intermixed with yellow brown clay.


The starter dam is 30 feet in height and has a crest width of 20 feet. The dam was built by Bloomsdale Excavating Company. There was an engineering design constructed by a Bill Devitt. However, the plan was of little use since it was a general sketch drawing. No provision was made for engineering construction inspection.

The dam was constructed some 3 years ago. Barite operations have just recently begun. Mud is being deposited along the south edge of the starter dam. Mud has not been deposited along the entire length of the structure. Thus, leakage was rather high where gravel is exposed to water. In addition, there seems to be considerable leakage throughout the entire starter dam. However, no free running water is evident with one single and particularly important exception.

A backslope slide has occurred on the southern end of the dam. This slide apparently is related to the pipe that was placed in the structure during construction. The slide is located where one of the drainageways was present in the original valley. The slide was rotational in nature with the toe bulging as the result of movement of the red clay. Slime resembling barite mud is present downstream in the stream channel for some 500 feet. There is evidence that water had percolated through the starter dam for some time and washing fine textured materials from the valley bottom downstream in the stream channel. Repairs were made by pushing dirt up on top of the slide. This has increased pore water pressure and will further weaken the dam.

RECOMMENDATIONS:

All of the material pushed up on the slides should be removed. The toe of the dam should be buttressed by a free draining berm of rock. Recommendations are also made that the mud be spread by flume along the entire crest with the dam. This would aid in sealing the gravels.



Dr. J. Hadley Williams, Chief  
Applied Engineering & Urban Geology  
Missouri Geological Survey  
September 23, 1975